



**CONTRACT #6240**

**DESIGN-BUILD SERVICES  
FOR  
LIRR EXPANSION PROJECT  
FROM FLORAL PARK TO HICKSVILLE**

**CONFORMED DOCUMENTS**

**VOLUME 6  
ENVIRONMENTAL COMPLIANCE PLAN**

**December 27, 2017**

A stylized signature in blue ink, consisting of a large, sweeping 'A' shape with a vertical line extending downwards from the center.

A handwritten signature in black ink, appearing to be the initials "DWC" written in a cursive, flowing style.

This page is not used.

## Table of Contents

1.0 Additional Environmental Compliance Requirements..... 3

## **1.0 Additional Environmental Compliance Requirements**

Most environmental compliance requirements arising from the EIS process are included in the Technical Provisions and other Contract Documents.

Additional Environmental Compliance requirements arising from the EIS and findings are as follows:

### **1.1 Community Security Requirements**

- A. The Design-Builder shall create an active program of construction security to ensure community safety, including Roving Security during off-work hours and holidays.
- B. Construction fencing shall be uniform green tennis mesh or printed mesh with artwork as approved by the Railroad.
- C. Develop and employ rodent control measures.

### **1.2 Construction Materials**

- A. Safely store construction materials in neat piles.

### **1.3 Parking Requirements for Design-Builder Personnel**

- A. No parking of personal construction worker vehicles shall be allowed on residential streets. The Design-Builder shall provide satellite parking for construction workers.

### **1.4 Directional Lighting**

- A. Use directional lighting to protect residences from light pollution.

### **1.5 Pedestrian Access**

- A. The Design-Builder shall provide and maintain pedestrian access at New Hyde Park Road at all times during the grade crossings construction.

### **1.6 Floral Park**

- A. The Design-Builder shall schedule construction in consultation with the Village to (i) avoid all disruptive work (e.g., pile driving, use of heavy equipment such as excavators and backhoes) adjacent to the Village pool during the peak season (Friday before memorial Day through Labor Day), and limit work near the pool during that period to non-disruptive work and normal LIRR operation and maintenance work; and (ii) otherwise minimize, to the extent practicable, the impact of Project work on the use of the Village recreation center and ballfields. The Design-Builder shall cease all construction activity near the pool on April 15 of each year to the opening of the peak pool season, to allow for the Village to inspect the pool and take any necessary corrective action prior to the peak pool season beginning.

**END**